



Port of San Francisco

Pier 26 Fire Water Pipe Replacement

OVERVIEW

This project will address the underdeck fire water supply lines to Pier 26. The existing underdeck piping system is heavily corroded and is leaking at multiple locations. There is a high probability of major failure which will result in loss of fire protection system at Pier 26 and significant discharge of potable water into the Bay (an environmental concern).

The estimate for construction is \$675,000.

SCHEDULE

Activity	Target Date*
Commence Contract Advertisement	Q3 2023
Pre-Bid Conference	Q3 2023
Due Date	Q3 2023
Notice to Proceed	Q4 2023

*Subject to change

PROJECT SCOPE

Removal of existing underdeck 12-inch fire water supply piping and associated hangers and bracing. Installation of new underdeck fire water supply piping and associated hangers and bracing. Installation of above deck backflow prevention assembly and bollards. And replacement of underground landside piping from backflow prevention assembly to seawall penetration point.

Major Categories of Work

- Construction (landside and marine)
- Plumbing

FOR MORE INFORMATION

CONTACT: Simon Betsalel, simon.betsalel@sfport.com, 415.609.8549